
Richards Consulting & Associates Limited

R.R.3

Red Deer, Alberta T4N 5E3

Phone: 403-886-2919 Fax: 403-886-2733

PROJECT: Maintenance Shop, Lac La Biche County, AB

THIS ADDENDUM FORMS PART OF, AND WILL BE ADDED TO, THE FINAL SET OF DRAWINGS FOR THIS PROJECT. THE PROJECT WILL NOT BE CONSIDERED COMPLETED, AND THE ENGINEER SHALL NOT SUPPLY A CERTIFICATE OF COMPLETION FOR AN OCCUPANCY PERMIT, UNTIL THE FOLLOWING REQUIREMENTS HAVE BEEN MET. ACKNOWLEDGMENT OF THE RECEIPT OF THIS ADDENDUM SHALL BE SENT TO RICHARDS CONSULTING & ASSOCIATES LIMITED.

- 1) Minimum requirements for 2001 NECB have been added to the A5 sheet. R values of insulation listed in assemblies now meet the requirements.
- 2) Building Code Analysis on the cover page had been revised.
- 3) Catwalk height has been added to detail 3 on S2.2.
- 4) Discrepancies between wall and roof cladding had been made consistent throughout the drawings. The walls are clad with 26 GA. Corrugated metal, and the roof is clad in 24 GA.
- 5) A note has been added to the A3.0 sheet regarding the sumps and who will be supplying them.
- 6) Door schedule had been revised on the A5 sheet
- 7) The opening date of the bid has been changed from August 15, 2017 to August 22, 2017.
- 8) Climatic information has been updated on the "S1" sheet.
- 9) 26 GA. Liner panel has been added to the "W1" wall assembly.

End of Addendum