

2018 Hamlet Street Resurfacing Program

		Width (m)	Length (m)	Milling (m2)	Lift Thickness	ACP (tonnes)
A	105 St(from 101 Ave to 101B Ave)	11	320	1,280	50	465
B	104 St (from 101B Ave to Churchill Dr)	11.1	400	1,600	50	586
C	103 St(from 101 Ave to 101B Ave)	11.2	70	280	50	103
D	101A Ave(from 101 Ave to 104 St)	12.7	145	580	50	243
E	101B Ave(from 101 Ave to 103 St)	12.7	110	440	50	184
H	91 Ave(from Hwy 36 to 95 St)	13	350	1,400	50	601
J	Crescent Heights(from 96st going east)	10.2	150	600	50	202
R	Misc. Laneways	5	400	1,600	50	264
S	Summit Heights Truck Fill	7	95	-	100	160
T	Dumasfield Rink	16.5	41	-	50	88
U	Walking Trail-Churchill Drive	2.35	800	-	35	180
V	Public Dock Access	2.3	15	-	50	8
	Misc. Repairs					150
	Total Quantities			6,180		2,384

Miscellaneous Repairs refers to asphalt mix required for levelling and or utility cuts. The repair of utility cuts involves removal of the existing fill and replacing the fill with asphalt mix. Any additional work required to facilitate work not identified herein shall be paid as "Extra Work" and rates shall be in accordance with the most recent edition of the ARHCA rental rate guide.